



Advanced Oxidation Plant at the Tucson International Airport Area Groundwater Remediation Project (TARP)



April 23, 2015

Presentation Outline


- History of TARP & 1,4-dioxane chronology
- Overview of pilot testing and design
- Facility construction
- Dedication Event
- Startup and operational experience



History of TARP & 1,4-dioxane chronology


TCE Discovery and Investigation

- 1981** TCE contamination discovered by EPA and Tucson Water in Tucson Airport area wells.
- 11 City wells and other private wells shut down
- 1982** EPA adds TAA site to Superfund National Priorities List
- 1985** CERCLA Remedial Investigation completed.
- Approx. 4-mile by 1-mile plume delineated
- 1988** CERCLA Feasibility Study for north area (TARP) completed; EPA issues Record of Decision



Groundwater Remedy Implemented

- 1990** Settling Parties enter into Consent Decree with EPA
- 1991-1994** Design & construction of wellfields, pipelines, and central treatment plant
- 1994** Nine remediation wells and packed column aeration facility become operational
- 1995** EPA-sponsored Unified Community Advisory Board (UCAB) formed




1,4-Dioxane Discovery & Early Efforts


2002 1,4-dioxane initially detected; routine monitoring commenced

2003 Initial conceptual studies for 1,4-dioxane treatment at TARP

2003 Blending efforts initiated by Tucson Water to target $\leq 3 \mu\text{g/L}$ at the entry point to the distribution system (EPDS)



Blending Approach




Contingency Preparations

2005 Contingency Plan developed for TARP operations to manage 1,4-dioxane

2009 Advanced Oxidation Process (AOP) Treatment Evaluation conducted

2010 AOP Pilot Treatability Testing conducted




Regulatory Developments & Treatment Implementation

2010 EPA publishes revised Toxicological Evaluation for 1,4-dioxane in August

2011 EPA publishes new Drinking Water Health Advisory for 1,4-dioxane (0.35 µg/L at 1×10^{-6} excess lifetime cancer risk level)

2011 AOP preliminary design

2011- AOP design and construction
2013



Overview of pilot testing and design

Pilot Testing Objectives

Ability to remove 1,4-dioxane

Generate site-specific data

Evaluate byproduct formation

Peroxide quenching methods

Operating experience

Select

1,4-dioxane
treatment
technology

Hydrogen
peroxide
quenching
method

Three 1,4-dioxane Treatment Technologies Evaluated



Ozone-Peroxide



Low Pressure High Output (LPHO) UV-Peroxide



Medium Pressure (MP) UV-Peroxide

Two Peroxide Quenching Methods Evaluated



Chemical quenching

- Common treatment chemicals



Catalytic quenching

- Granular activated carbon

LPHO UV-Peroxide Technology Selected for TARP

Exceeded
treatment goals for
1,4-dioxane
reduction

No formation of
bromate or
unregulated
byproducts

Operational
simplicity

Demonstrated full-
scale drinking
water installations

Peroxide Quenching Using GAC Selected for TARP

Complete quenching at low contact times and high surface loading rates

Potential to decrease byproducts

- Assimilable Organic Carbon (AOC)
- TTHM precursors
- Other unregulated contaminants

Operational and water quality stability advantages over chemical quenching

Objectives for Full-scale Facility

- Provide 1,4-dioxane treatment at the TARP WTP, eliminating need for blending
- Install AOP treatment upstream of existing packed column aeration
- Design for full-flow treatment capacity, with flexibility for partial stream treatment
- Optimize operating variables
 - ✓ Amount of flow directed to AOP
 - ✓ Power and hydrogen peroxide costs

Major Equipment Selection



UV-Peroxide AOP Reactors

- In-line pressure reactors



GAC Contactors



- 10-foot diameter pressure vessels
- Catalytic carbon

Schematic

ADVANCED OXIDATION PROCESS (AOP)

A proven technology that combines ultraviolet (UV) light with hydrogen peroxide to create a strong oxidant that removes 1,4-dioxane from water

New AOP Water Treatment Facility



The UV reactors remove 1,4-dioxane by oxidation



Granular activated carbon (GAC) removes any hydrogen peroxide left in treated water

Site Layout



Facility construction

Technical Implementation

- Contracting approach
 - Construction manager at risk
 - Separate GMPs for long-lead equipment purchase and general construction
- Schedule
 - Major equipment: GMP-1 awarded July 2012
 - Construction: GMP-2 awarded Sept. 2012
 - Substantial completion: November 2013
 - Final completion: February 2014

Construction Site Overview




UV Building/Equipment Construction




Completed Facility



Completed Facility



Dedication Event *January 15, 2014*



AOP Dedication

January 15, 2014



AOP Dedication

January 15, 2014



Startup and operational experience


Operational Experience During Year 1

- Consistent contaminant destruction:
 - 1,4-dioxane $<0.1 \mu\text{g/L}$
 - TCE $<0.5 \mu\text{g/L}$
- Misc. adjustments in AOP control logic and setpoints for operational stability
- Robust peroxide quenching by GAC with little O&M attention needed
- Extremely low backwash frequency required for GAC



Full-scale Performance: 1,4-dioxane


1,4-Dioxane Average Concentration (12/1/14-3/25/15)*



*Note: only includes data from time periods when AOP Facility was in operation

Full-scale Performance: TCE

TCE (12/2/14 - 3/25/15)



Questions



Jeff Biggs, Tucson Water
jeff.biggs@tucsonaz.gov

Jim Dettmer, ARCADIS
jim.dettmer@arcadis-us.com